



## **Regional Municipality of Durham – Housing Services**

### **IQ-0081-2026 Scope of Work & Specification**

#### **Attic Insulation Replacement**

**1910 Faylee Crescent, Pickering**

#### **Scope of Work**

Supply all labour, materials, equipment, and supervision required to remove existing attic insulation, air-seal all attic penetrations, and supply and install new loose-fill fiberglass insulation to achieve a minimum thermal resistance of R-70 (approximately 13,700 square feet of attic area).

Scope of work shall also include the supply and installation of ventilation baffles and the insulation and weather-sealing of all attic access hatches, as outlined in the project specifications.

The Contractor shall verify all existing site conditions, including attic configuration, insulation type, and measurements, prior to submission of pricing.

Mandatory site meeting: February 17, 2026, at 10:00 a.m.

#### **Specification**

##### **1. General**

- Work to be completed during regular business hours: Monday to Friday, 8:30 AM – 4:30 PM, unless otherwise approved by the Project Manager.
- Contractor to provide a schedule including phases of removal and installation, with coordination to minimize disruption to other trades.
- Contractor shall ensure all areas are clean with no tripping hazards during and after working hours.
- All debris to be removed daily. No onsite dumping or storage of removed materials is permitted.
- Contractor to restore safe site conditions daily and clean all affected areas at completion.
- Damages to building finishes, access panels, or structures must be repaired by the contractor at no additional cost.
- Inspect and repair all fire separations that were damaged before or during removal and installation ensuring continuous fire rating.

- Coordinate all access (attic, hatch, ladder locations) and safety measures with the site supervisor or property management.
- Contractor to submit MSDS sheets for all materials and adhere to applicable safety and environmental codes.

## **2. Removal of Existing Insulation**

- Carefully remove and dispose of all existing insulation from attic spaces.
- Removal includes insulation in hard-to-access corners, around penetrations, and above attic hatches.
- Ensure all insulation is fully removed to expose attic deck/sheathing before proceeding.
- Implement dust control and safe removal procedures as per Occupational Health & Safety guidelines, including use of HEPA vacuum systems.
- Bag and remove insulation material off-site; no on-site storage permitted.

## **3. Air Sealing**

- Perform thorough attic air sealing prior to insulation installation. Seal all penetrations using non-combustible fire-rated sealant.
  1. Plumbing stacks
  2. Electrical wires
  3. HVAC ducts and boots
  4. Top plates, open cavities, and gaps
- Install IC-rated light fixtures covers as required
- Weatherstrip and insulate attic hatches using rigid foam board, R value to match new insulation. Construct insulation dams around hatch area as required to maintain depth. Attic hatch insulation and dam to be painted with fire resistance paint.

## **4. Ventilation Preparation – Baffles**

- Install ventilation baffles in each rafter bay adjacent to soffits prior to insulation *DCI SmartBaffle® corrugated plastic* (16" and 24" O.C. as required) or equivalent as per approval
- Installation Requirements:
  - 1 baffle per rafter cavity at soffit edge
  - Extend baffles 16 to 24" past insulation into attic space
  - Maintain a minimum 1" - 2" continuous air gap between insulation and roof sheathing
  - Where required, install rigid blocking dams to prevent insulation from obstructing air pathways

## 5. Insulation Installation – Blown-In Fiberglass

- Supply and install loose-fill fiberglass insulation to achieve a minimum of R-70 (25" depth) uniformly across attic space. *Owens Corning PROPINK® L77* loose-fill fiberglass (or equivalent as per approval)
- Use mechanical blowing equipment to ensure consistent coverage and avoid settling voids.
- Apply insulation behind and around obstacles (e.g., trusses, mechanicals) without compressing.
- Install depth markers (graduated rulers) every 300 sq. ft. or per manufacturer recommendation.
- Maintain a continuous insulation layer with proper air space clearance near ventilation baffles.
- Ensure insulation is not piled against recessed lights unless fixtures are IC-rated and air-sealed.
- Build insulation dams around attic access, chimneys, recessed lights (if applicable)

## 6. Specifications & Materials

- Insulation - *Owens Corning PROPINK® L77* loose-fill fiberglass (or equivalent as per approval)
  - R-Value: R-3 per inch (25")
- Ventilation Baffles - *DCI SmartBaffle® corrugated plastic* (16" and 24" O.C. as required) or equivalent as per approval)

## 7. Warranty

- Contractor shall provide a 1-year warranty of workmanship.

## Appendix A – Existing Conditions

