



Centre d'excellence en approvisionnement
FRANCOachat

REQUEST FOR QUOTATION

#26-27 - RFQ - Interior Renovations - Collège Français - CSViamonde

ADDENDUM #2

Issue Date: March 9th, 2026

Submission Date: April 1st, 2026 at 2:00:00 p.m. (local time)

The Competitive procurement process Coordinator is:
Kyle Patterson
Centre d'excellence en approvisionnement FRANCOachat
1, promenade Vanier, bureau 102
Welland, ON L3B 1A1
Telephone: (905) 732-9435 ext. #7
Email: info@FRANCOachat.ca

#26-27 - RFQ - Interior Renovations - Collège Francais – CSViamonde

ADDENDUM #2

March 17, 2026

This addendum will form part of the terms, conditions and specifications outlined in the Request for Quotation - #26-27 - RFQ - Interior Renovations - Collège Francais - CSViamonde. All other components of the RFQ shall remain as provided.

Section #1 – Document Addition

Addition:

Add: Architectural Addendum 001 - Interior Renovations - Collège Francais - RFQ #26-27.pdf

(Please see document below)

*****END OF ADDENDUM #2*****



ADDENDUM

ADD 01

Project Name: Viamonde College Francais

Project Address: 100 Carlton Street

Project No. 25-012

Prepared By: Tiffany Tse

Date: 2026.03.16

ADD No. 01

No Pages : 2

Owner: : Conseil Scolaire Viamond

The following information supplements and / or supersedes the bid documents issued on the tender submission date noted above and all previously issued addenda. This addendum is to be read, interpreted, and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above named project to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject to disqualification.

1.0 General Answers to Questions

1.1 Please clarify if construction activities can be performed in regular business hours.

Response: Yes

2.0 Architectural items

2.1 Drawing A7.1 - Door Schedule noted doors are SC with PT-2A finishes, please confirm that all doors are paint grade wood doors; and specifications section 08 11 00 noted metal doors, please confirm that all doors are wood doors, no metal doors.

Response: all doors to be painted hollow metal, per specification

2.2 Drawing A2.1, Room-134, if shower curtain is required? If yes, please provide specifications

Response - Frost 1144-503 and shower curtain hooks (114-501L) on rod

2.3 Drawing A2.1 note# 12 noted new bottle filler, please clarify if new bottle filler to be part of General Contractor's scope, if yes, please provide new bottle filler station specifications.

Response: Bottle filler spec is included in the Plumbing Fixture Schedule on sheet M3 item DF-1. However it should be updated to be Elkay Model VRCDWSK (non refrigerated and non filtered)

2.4 Drawing A2.1 note #16 noted acrylic signage, please provide acrylic signage drawings for pricing purpose, and section 10 80 00 noted acrylic signage, but no acrylic signage specifications provided, please update.

Response: Provide allowance of \$8,000 for signage

2.5 Drawing 20/A8.0, please clarify the height from ceiling to deck.

Response: based on the existing drawings from the floor slab to the underside of the deck is +/-4m

3.0 Mechanical Items + Electrical

3.1 Please clarify if any sprinklers scope? I can't find sprinklers drawings

Response: There are no sprinklers in the change room area



ADDENDUM

ADD 01

3.2 Please provide base building fire alarm vendor contact information

Response: ML FIRE 905-841-3888 / 905-889-8276
website: www.mlfire.com
email: service@mlfire.com

3.3 Please provide base building BAS controls vendor contact information.

Response: VIRIDIAN , ERIC SHING ESSHING@VIRIDIANAUTOMATION.COM

3.4 If electrical demolition drawings can be provided for pricing purpose?

Response: Demo drawings are not available. If clarifications are required after the site visit please let us know.

3.5 Drawing E-2 note# 12, please provide heater specifications for pricing purpose.

Response: The note specifies the type of BBH from Stelpro (CBB series) - in addition it mentions the size of the breaker (which indicates the KW) and for them to forward a shop drawing for approval. It was not possible to verify the exact brand or KW size of what is existing - there are different size breakers in the panel feeding 'BBH'. Please verify the size (which breaker) and confirm. The CBB comes in a 15A2P and a 20A2P (again specified within the note). CBB9078W (tamper proof) CBBT22 could be used as a baseline for pricing.

4.0 Structural

4.1 Drawing S1.01 note #1 noted new CMU partition bear on 4" slab on grade, please clarify if the ground floor is slab on grade? As there are three (3) levels of underground parking... and drawing Note#5 noted to patch slab for plumbing refer to 2/S0.02, if there are underground parking, then detail 2/S0.02 is not correct?

Response: The parking is under the school building. The change rooms are in a separate building that was constructed later, it is slab on grade.