



Centre d'excellence en approvisionnement

FRANCOachat

REQUEST FOR QUOTATION

#26-07 - RFQ - Interior & Exterior Lighting upgrade - École Patricia-Picknell & École Du Chêne – CSViamonde

ADDENDUM #1

Issue Date: March 12th, 2026

Submission Date: April 9th, 2026 at 2:00:00 p.m. (local time)

The Competitive procurement process Coordinator is:
Kyle Patterson
Centre d'excellence en approvisionnement FRANCOachat
1, promenade Vanier, bureau 102
Welland, ON L3B 1A1
Telephone: (905) 732-9435 ext. #7
Email: info@FRANCOachat.ca

#26-07 - RFQ - Interior & Exterior Lighting upgrade - École Patricia-Picknell & École Du Chêne - CSViamonde

ADDENDUM #1

March 23, 2026

This addendum will form part of the terms, conditions and specifications outlined in the Request for Quotation - #26-07 - RFQ - Interior & Exterior Lighting upgrade - École Patricia-Picknell & École Du Chêne - CSViamonde. All other components of the RFQ shall remain as provided.

Section #1 – Document Addition

Addition:

Add: Appendix E3 - Architectural Specifications - École Élémentaire du Chêne - RFQ #26-07.pdf

(Please see document below)

*****END OF ADDENDUM #1*****

PART 1 GENERAL

1.1 General

- .1 Conform to the requirements of Division 1.

1.2 Related Sections

- .1 Section 09 21 16 Gypsum Board
- .2 Section 09 53 00 Acoustical Suspension

1.3 References

- .1 ASTM International (ASTM)
 - .1 ASTM C423-23 Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
 - .2 ASTM E84-24 Standard Test Method for Surface Burning Characteristics of Building Materials
 - .3 ASTM E1264-22 Standard Classification for Acoustical Ceiling Products
 - .4 ASTM E1414/E1414M-21a Standard Test Method for Airborne Sound Attenuation Between Rooms Sharing a Common Ceiling Plenum
 - .5 ASTM E1477-98a(2022) Standard Test Method for Luminous Reflectance Factor of Acoustical Materials by Use of Integrating-Sphere Reflectometers
- .2 Underwriters Laboratories of Canada (ULC)
 - .1 ULC 102-2018 Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.

1.4 Submittals

- .1 Make submittals in accordance with Section 01 33 00 – Submittal Procedures.
- .2 Product Data: Submit manufacturer's technical data for each type of acoustical ceiling unit and suspension system required.
 - .1 Acoustical Certifications: Manufacturer's certifications that products comply with specified requirements, including laboratory reports showing compliance with specified tests and standards. For acoustical performance, each carton of material must carry an approved independent laboratory classification of NRC, CAC, and AC.
- .3 Submit duplicate 300 x 300 mm samples of each type of acoustical units.
- .4 Provide maintenance data for acoustic panel ceilings for incorporation into Operation and Maintenance Manual specified in Section 01 78 00 – Closeout Submittals.

1.5 Quality Assurance

- .1 Single-Source Responsibility: Provide acoustical panel units and grid components by a single manufacturer.
- .2 Coordination of Work: Coordinate acoustical ceiling work with installers of related work including, but not limited to building insulation, gypsum board, light fixtures, mechanical systems, electrical systems, and sprinklers.
- .3 Mock-up:
 - .1 Construct mock-ups in accordance with Section 01 45 00 - Quality Control.

- .2 Construct mock-up 10 m² minimum of acoustical panel tile ceiling including one inside corner and one outside corner.
- .3 Construct mock-up where directed.
- .4 Allow 48 hours for inspection of mock-up by Consultant before proceeding with ceiling work.
- .5 When accepted, mock-up will demonstrate minimum standard for this work. Mock-up may remain as part of the finished work.

1.6 Project Conditions

- .1 Permit wet work to dry before beginning to install.
- .2 Maintain uniform minimum temperature of 15° C and humidity of 20-40% before and during installation.
- .3 Store materials in work area 48 hours prior to installation.
- .4 Building areas to receive ceilings shall be free of construction dust and debris.

1.7 Performance Requirements

- .1 Fire Performance Characteristics: Identify acoustical ceiling components with appropriate markings of applicable testing and inspecting organization.
 - .1 Surface Burning Characteristics: As follows, tested per ASTM E84 and complying with ASTM E1264 Classification.
 - .2 Fire Resistance: As follows tested per ASTM E119 and listed in the appropriate floor or roof design in the Underwriters Laboratories Fire Resistance Directory
- .2 Seismic Performance: Acoustical ceiling shall withstand the effects of earthquake motions determined according to applicable code.

1.8

Shipping, Handling and Storage

- .1 Refer to Section 01 61 00 – Common Product Requirements.
- .2 Deliver, handle and store materials in accordance with manufacturer's printed instructions.
- .3 Protect on site stored or installed absorptive material from moisture damage.

1.9 Waste Management and Disposal

- .1 Refer to Section 01 74 19 – Construction Waste Management and Disposal.

1.10 Extra Materials

- .1 Provide extra materials of acoustic units in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Provide acoustical units amounting to 5% of gross ceiling area for each pattern and type required for project.
- .3 Ensure extra materials are from same production run as installed materials.

PART 2 PRODUCTS

2.1 Materials

- .1 Acoustic units for suspended ceiling system: to ASTM E1264
- .2 Panel Type 1: CGC Fissured.
 - .1 Class A.
 - .2 Composition: Water Felted Mineral Fiber
 - .3 Pattern regular fissured.
 - .4 Texture: medium.
 - .5 Flame spread: ASTM E1264, Class A (U.L.C.), 25 or less.
 - .6 Smoke developed 50 or less in accordance with ULC 102.
 - .7 Noise Reduction Coefficient (NRC): ASTM C423; Classified with UL label, 0.55
 - .8 Ceiling Attenuation Class (CAC): ASTM C1414; Classified with UL label, 35
 - .9 Light Reflectance (LR) range of 0.81 to ASTM E1477.
 - .10 Dimensional Stability: Standard
 - .11 Edge Profile: Square Lay-In
 - .12 Colour: White.
 - .13 Size 610 x 1219 x 16 mm thick.
 - .14 Shape flat.
 - .15 Surface coverings: Ecolabel certified paint.
- .3 Alternate manufacturer: Products as manufactured by the following are acceptable, subject to Consultants approval of style, finish, performance characteristics and texture:
 - .1 Armstrong Industries
 - .2 Certainteed
- .4 Ceiling Suspension System: Existing

PART 3 EXECUTION

3.1 Examination

- .1 Do not install acoustical panels until work above ceiling has been inspected by Consultant.

3.2 Installation

- .1 Co-ordinate with Section 09 53 00 - Acoustical Suspension.
- .2 Coordinate layout and installation of ceilings with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, and fire-suppression system.
- .3 Install acoustical panels and tiles in ceiling suspension system.
- .4 Install acoustical units parallel to building lines with edge unit not less than 50% of unit width, with directional pattern running in same direction. Refer to reflected ceiling plan.
- .5 Scribe acoustic units to fit adjacent work. Butt joints tight, terminate edges with moulding.

3.3 Cleaning

- .1 Proceed in accordance with Section 01 74 11 – Cleaning.

End of Section

PART 1 GENERAL

1.1 Section Includes

- .1 Progressive Cleaning
- .2 Final Cleaning

1.2 References

- .1 National Fire Protection Association (NFPA)
 - .1 NFPA 241-22 Standard for Safeguarding Construction, Alteration, and Demolition Operations.

1.3 Project Cleanliness

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by the Owner. Do not burn waste materials on site.
- .3 Clear snow and ice from access to building, bank/pile snow in designated areas only.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris.
- .6 Provide and use clearly marked separate bins for recycling.
- .7 Clean interior areas prior to start of finishing work and maintain areas free of dust and other contaminants during finishing operations.
- .8 Store volatile waste in covered metal containers and remove from premises at end of each working day.
- .9 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .10 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

PART 2 PRODUCTS

2.1 Products

- .1 All cleaning materials and products shall be low VOC type. Submit list of cleaning products including SDS for approval prior to commencement of cleaning operations.
- .2 Use only cleaning materials recommended by manufacturer of surface to be cleaned and recommended by cleaning material manufacturer.

PART 3 EXECUTION

3.1 Final Cleaning

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Clean and polish glass, mirrors, hardware, wall tile, stainless steel, chrome, porcelain enamel, baked enamel, plastic laminate, and mechanical and electrical fixtures. Replace broken, scratched or disfigured glass.
- .5 Remove stains, spots, marks and dirt from decorative work, electrical and mechanical fixtures, furniture fitments, walls, floors and ceilings.
- .6 Clean lighting reflectors, lenses, and other lighting surfaces. Clean and/or replace lamps, light fixtures, grilles and lenses.
- .7 HEPA vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .8 Thoroughly vacuum clean interior of electrical equipment.
- .9 Wax, seal, shampoo or prepare floor finishes, as recommended by manufacturer.
- .10 Clean and seal concrete floor surfaces with non-skid matte sealer.
- .11 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .12 Clean equipment and fixtures to a sanitary condition; clean or replace filters of mechanical equipment.
- .13 Broom clean and wash exterior paved areas, walks, steps and surfaces; rake clean other surfaces of grounds.
- .14 Remove dirt and other disfiguration from exterior surfaces.
- .15 Clean and sweep roofs. Clear all drains, scuppers, gutters and downspouts.
- .16 Remove debris and surplus materials from crawl spaces and other accessible concealed spaces.
- .17 Remove snow and ice from access to building.
- .18 Under direction of Consultant, aim adjustable luminaires.

3.2 Waste Management and Disposal

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 19 – Construction Waste Management and Disposal.

End of Section

PART 1 GENERAL

1.1 Section Includes

- .1 References.
- .2 Submittals.
- .3 Definitions.
- .4 Waste Management Goals for the Project.
- .5 Documents.
- .6 Waste Management Plan.
- .7 Materials Source Separation Program.
- .8 Disposal of Wastes.
- .9 Scheduling.
- .10 Storage, Handling and Protection.
- .11 Application.
- .12 Diversion of Materials.

1.2 References

- .1 O. Reg. 102/94 Waste Audits and Waste Reduction Work Plans.
- .2 O. Reg. 278/05 Occupational Health and Safety Act

1.3 Submittals

- .1 Make submittals in accordance with Section 01 33 00 – Submittal Procedures.
- .2 Submit a completed Waste Management Plan (WMP) prior to project start-up.

1.4 Definitions

- .1 Waste Management Plan (WMP): Contractor's approved overall strategy for waste management including waste reduction workplan and materials source separation program.
- .2 Materials Source Separation Program (MSSP): Consists of a series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .3 Separate Condition: Refers to waste sorted into individual types.

1.5 Waste Management Goals for the Project

- .1 The Owner has established that this Project shall generate the least amount of waste possible and that processes shall be employed that ensure the generation of as little waste as possible including prevention of damage due to mishandling, improper storage, contamination, inadequate protection or other factors as well as minimizing over packaging and poor quantity estimating.
- .2 Of the waste that is generated, the waste materials designated in this specification shall be salvaged for reuse and or recycling. Waste disposal in landfills or incinerators shall be minimized.

1.6 Waste Management Plan

- .1 Waste Management Plan: Submit a Waste Management Plan within 10 calendar days after receipt of Notice of Award of Contract, or prior to any waste removal, whichever occurs sooner. The Plan shall contain the following:
 - .1 Analysis of the proposed job site waste to be generated, including the types of recyclable and waste materials generated (by volume or weight). In the case of demolition, a list of each item proposed to be salvaged during the course of the project should also be prepared
 - .2 Alternatives to Land Filling: Contractor shall designate responsibility for preparing a list of each material proposed to be salvaged, reused, or recycled during the course of the Project.
- .2 Post WMP or summary where workers at site are able to review its content.

1.7 Materials Source Separation Program

- .1 The Waste Management Plan shall include a Source Separation Program for recyclable waste and shall be in accordance with the established policies currently in place at the local Municipality, and the requirements of O. Reg. 102/94.
- .2 Prepare MSSP and have ready for use prior to project start-up.
- .3 Implement MSSP for waste generated on project in compliance with approved methods and as approved by Consultant.
- .4 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and/or recyclable materials.
- .5 Provide containers to deposit reusable and/or recyclable materials.
- .6 Locate containers to facilitate deposit of materials without hindering daily operations.
- .7 Locate separated materials in areas which minimize material damage.
- .8 Collect, handle, store on-site, and transport off-site, salvaged materials in separate condition.

1.8 Disposal of Wastes

- .1 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .2 Provide appropriate on-site containers for collection of waste materials and debris. Containers for volatile wastes shall be closed containers and shall be removed from site daily.
- .3 Provide and use clearly marked separate bins for recycling.
- .4 Remove waste materials from site at regularly scheduled times or dispose of as directed by Consultant. Do not burn waste materials on site.
- .5 Remove waste material and debris from site and deposit in waste container at end of each working day.
- .6 Do not permit waste to accumulate onsite.

- .7 Burying of rubbish and waste materials is prohibited.
- .8 Disposal of waste into waterways, storm or sanitary sewers is prohibited.

1.9 Scheduling

- .1 Coordinate work with other activities at site to ensure timely and orderly progress of the Work.

1.10 Storage, Handling and Protection

- .1 Store, materials to be reused, recycled and salvaged in locations as directed by Owner.
- .2 Materials from building demolition to be salvaged or re-used are to be removed and salvaged.
- .3 Unless specified otherwise, materials for removal become Contractor's property.

PART 2 PRODUCTS

2.1 Not Used

- .1 Not used

PART 3 EXECUTION

3.1 Application

- .1 Do work in compliance with Waste Management Plan.
- .2 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.
- .3 Source separate materials to be reused/recycled into specified sort areas.

3.2 Designated Substances

- .1 All designated substances abatement, removal and disposal shall be completed in accordance with O. Reg 278/05 and all other applicable legislation.

3.3 Diversion of Materials

- .1 Separate materials from general waste stream and stockpile in separate piles or containers, to approval of Owner, and consistent with applicable fire regulations. Mark containers or stockpile areas.
- .2 On-site sale of materials is not permitted.

End of Section

PART 1 GENERAL

1.1 Section Includes

- .1 Administrative procedures preceding preliminary and final inspections of Work.

1.2 References

- .1 Canadian Construction Documents Committee
 - .1 CCDC 2-2020 Stipulated Price Contract including Supplementary Conditions.
 - .2 OAA/OGCA Document 100 - Recommended Procedures Regarding Substantial Performance of Construction Contracts and Completion Takeover of Projects.
 - .3 The Construction Act.

1.3 Inspection and Declaration

- .1 Contractor's Inspection: The Contractor shall conduct an inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents. Submit duplicate copies of the deficiency list to the Owner and Consultant.
 - .1 Notify Consultant in writing of satisfactory completion of Contractor's Inspection and that corrections have been made.
 - .2 Request Consultant's review.
- .2 Consultant's Review: Consultant and Contractor will perform review of Work to identify obvious defects or deficiencies. Contractor shall correct Work accordingly.
- .3 Completion: submit written certificate that following have been performed:
 - .1 Work has been completed and inspected for compliance with Contract Documents.
 - .2 Defects have been corrected and deficiencies have been completed.
 - .3 Equipment and systems have been tested, adjusted and balanced and are fully operational.
 - .4 Certificates required by Boiler Inspection Branch, Fire Commissioner, Utility companies, TSSA, ESA and other regulatory agencies have been submitted.
 - .5 Operation of systems have been demonstrated to Owner's personnel.
 - .6 Work is complete and ready for Final Review by the Consultant.
- .4 Final Inspection: when items noted above are completed, request final review of Work by Consultant, and Contractor. If Work is deemed incomplete by the Consultant, complete outstanding items and request re-review.
- .5 Declaration of Substantial Performance: when Consultant consider deficiencies and defects have been corrected and it appears requirements of Contract have been substantially performed, make application for certificate of Substantial Performance. Refer to CCDC 2, General Conditions Article GC 5.4 - Substantial Performance of Work and Payment of Holdback for specifics to application.
- .6 Commencement of Lien and Warranty Periods: date of Owner's acceptance of submitted declaration of Substantial Performance shall be date for commencement for warranty period and commencement of lien period unless required otherwise by lien statute of Place of Work.
- .7 Final Payment: When Consultant considers final deficiencies and defects have been corrected and it appears requirements of Contract have been totally performed, make application for final payment. Refer to CCDC 2, General Conditions Article GC 5.5 – Final Payment for specifics to application.

- .8 Payment of Holdback: After issuance of certificate of Substantial Performance of Work, submit an application for payment of holdback amount in accordance with CCDC 2, General Conditions Article 5.4 - Substantial Performance of Work and Payment of Holdback.

PART 2 PRODUCTS

2.1 Not Used

- .1 Not used

PART 3 EXECUTION

3.1 Not Used

- .1 Not used

End of Section