

TITLEBLOCK 24x36 VERT ENG
PRINT DATE: 2026-03-16 4:41:33 PM
PATH: A:\work\Draws\DDSB\Accessibility Projects\A001199\Waverly PS-S23.rvt

GENERAL NOTES:

1. READ STRUCTURAL DRAWINGS IN CONJUNCTION WITH THE REMAINDER OF THE CONTRACT DRAWINGS AND DOCUMENTS.
2. VERIFY ALL DIMENSIONS ON THE STRUCTURAL DRAWINGS WITH THE REMAINDER OF THE CONTRACT DRAWINGS BEFORE CONSTRUCTION. ANY DISCREPANCIES OR ERRORS MUST BE REPORTED TO THE ENGINEER PRIOR TO STARTING THE WORK.
3. THE CONTRACTOR IS TO VERIFY ALL DIMENSIONS PRIOR TO COMMENCEMENT OF WORK. DO NOT SCALE FROM DRAWINGS. REPORT ANY DISCREPANCIES TO THE CONSULTANT FOR CLARIFICATION BEFORE PROCEEDING.
4. DESIGN LOADS INDICATED ARE UNFACTORED UNLESS NOTED OTHERWISE.
5. DESIGN LIVE LOADS FOR EACH PORTION OF THE STRUCTURE ARE SHOWN. DO NOT EXCEED THESE LOADS DURING CONSTRUCTION.
6. STRUCTURAL DESIGN IS BASED ON THE LATEST EDITION OF THE NATIONAL AND ONTARIO BUILDING CODES. SUBSTRUCTURES AND WATER RETAINING TANKS, RESERVOIRS AND CONDUITS HAVE BEEN DESIGNED IN ACCORDANCE WITH CODE REQUIREMENTS FOR ENVIRONMENTAL CONCRETE STRUCTURES (ACI) 350-06 EXCEPT WHERE IT WAS NOT CONSIDERED APPLICABLE.
7. FEATURES OF CONSTRUCTION NOT FULLY SHOWN ARE OF THE SAME CHARACTER AS THOSE NOTED FOR SIMILAR CONDITIONS.
8. COORDINATE PLACEMENT AND LOCATION OF ITEMS BY SUBSEQUENT TRADES. RELEVANT TRADES SHALL REVIEW PRIOR TO ERECTION AND/OR INSTALLATION.
9. REFER TO ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS FOR SMALL OPENINGS, SLEEVES, RECESSES, DEPRESSIONS, SUMPS, TRENCHES, CURBS, HOUSEKEEPING PADS, EQUIPMENT BASES, AND SLOPES NOT INDICATED ON THE STRUCTURAL DRAWINGS.
10. DO NOT SCALE DRAWINGS.
11. ALL CODES REFERENCED ARE TO BE THE LATEST VERSION AT THE DATE OF ISSUE.
12. SUBMIT DRAWINGS OF EXISTING BUILDING SHORING FOR REVIEW. DRAWINGS TO BE SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE PROVINCE OF ONTARIO.

FOUNDATION

1. THE DESIGN OF TEMPORARY WORKS IS THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTROL OF THE GROUND WATER SHALL BE CARRIED OUT BY A SPECIALIZED FOUNDATION CONSULTANT, ENGAGED BY THE CONTRACTOR. THE COSTS OF ANY ADDITION GEOTECHNICAL INVESTIGATION AND/OR TESTING IS INCIDENTAL TO THE WORK AND WILL NOT BE CONSIDERED AS EXTRA COST TO THE OWNER.
2. THE SPECIALIZED FOUNDATION CONSULTANTS SHALL BE RESPONSIBLE FOR THE DESIGN, INSTALLATION, TESTING, MONITORING AND, IF REQUIRED, REMOVAL OF TEMPORARY SHORING AND DEWATERING SYSTEMS.
3. BACKFILL AGAINST FOUNDATION WALL IN SUCH A MANNER THAT THE LEVEL OF BACKFILLING ON ONE SIDE OF THE WALL IS NEVER MORE THAN 450mm DIFFERENCE FROM THE LEVEL ON THE OTHER SIDE OF THE WALL UNLESS TEMPORARY SUPPORT FOR THE WALL IS PROVIDED.
4. SOFT AREAS UNCOVERED ON EXCAVATION SHALL BE SUB EXCAVATED TO SOUND MATERIAL AND FILLED WITH GRANULAR 'A' SOIL COMPACTED TO 100% STANDARD PROCTOR DRY DENSITY.
5. PLACE SLAB ON GRADE ON SOIL CAPABLE OF SUSTAINING 24 kPa WITHOUT SETTLEMENT RELATIVE TO THE BUILDING FOOTINGS.

STRUCTURAL STEEL:

1. COORDINATE WITH MECHANICAL ENGINEER, ELECTRICAL ENGINEER AND ALL SUB-TRADES WHOSE WORK AFFECTS THE DETAILING, FABRICATION AND ERECTION OF THE STRUCTURAL STEEL. DO NOT CUT OPENINGS IN STRUCTURAL STEEL MEMBERS WITHOUT APPROVAL OF ENGINEER.
2. PREPARE AND SUBMIT FULLY DETAILED AND DIMENSIONED DRAWINGS AND ERECTION DIAGRAMS. COPIES SHALL BE PROVIDED TO THE ENGINEER FOR REVIEW. ERECTION DRAWINGS SHALL BE SEALED BY THE FABRICATOR'S ENGINEER.
3. COPIES OF THE ERECTION AND FABRICATION DRAWINGS SHALL BE PROVIDED AS REQUIRED FOR THE OWNER'S FILE AND/OR THE MUNICIPALITY.
4. BOLTED CONNECTIONS SHALL BE MADE USING HIGH TENSILE STRENGTH BOLTS.
5. PROVIDE TEMPORARY BRACING NECESSARY TO KEEP THE STRUCTURE TRUE AND PLUMB DURING CONSTRUCTION UNTIL PERMANENT BRACING IS INSTALLED. BRACING DESIGN SHALL BE PROVIDED AND CERTIFIED BY FABRICATOR'S ENGINEER.
6. ALL CONNECTIONS TO BE STANDARD FRAME BEAM CONNECTIONS AND ARE TO BE DESIGNED AND CERTIFIED BY THE FABRICATOR'S ENGINEER AS PER CSA S16.1.
7. VARIATIONS FROM PLUMB AND LEVEL:
EXTERIOR COLUMNS, SPANDREL BEAMS, AND ANGLES: ± 3/3000
OTHER MEMBERS: ± 6/3000
8. STEEL SHALL BE THOROUGHLY CLEANED AND BE GIVEN ONE SHOP COAT OF ANTI-CORROSIVE PRIMER. AREAS AFFECTED BY WEATHERING, OR ANY OTHER DAMAGE SHALL HAVE THE RUST REMOVED AND BE "TOUCHED UP" IN THE FIELD. STEEL PERMANENTLY EXPOSED TO WEATHER SHALL BE HOT DIPPED GALVANIZED UNLESS NOTED ELSEWHERE. GALVANIZING SHALL BE REMOVED LOCALLY PRIOR TO ANY STRUCTURAL FIELD WELDING.

MATERIALS:

1. CONCRETE SLAB INFILL AND THICKENING SHALL BE 25 MPa, CLASS N.
CONCRETE PILE CAP AND FOUNDATION WALLS SHALL BE 35 MPa, CLASS N.
2. ALL REINFORCING BAR SHALL BE GRADE 400MPa, DEFORMED, CAN/CSA-G30.18.
3. CONCRETE BLOCK SHALL CONFORM TO THE LATEST EDITION OF THE RELEVANT CODES AND STANDARDS AND THE BLOCK STRENGTH SHALL BE 15MPa ON NET AREA.
4. MORTAR SHALL BE TYPE "S" UNLESS NOTED OTHERWISE.
5. CONCRETE FILL IN REINFORCED MASONRY SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 20MPa.
6. COLUMN BEARING GROUT SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 40MPa.
7. STRUCTURAL STEEL TO CONFORM TO CAN/CSA-G40.21, UNO.

W SECTIONS: GRADE 350W
L AND C SECTIONS: GRADE 350W
HSS SECTIONS: GRADE 350 CLASS 'H'
8. THE WELDING ELECTRODES SHALL CONFORM TO THE REQUIREMENTS OF CSA STANDARD W48 (LATEST EDITION).

MASONRY:

1. ALL MASONRY CONSTRUCTION SHALL CONFORM TO THE RELEVANT CODES AND STANDARD AS REQUIRED IN THE PROJECT SPECIFICATION.
2. THE MASONRY WORK HAS BEEN DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF THE APPLICABLE CODES AND STANDARDS AS REQUIRED BY THE PROJECT SPECIFICATIONS.
3. NO MASONRY WORK SHALL BE PERMITTED WITH THE TEMPERATURE BELOW 5°C UNLESS PROVISIONS ARE MADE FOR HEATING THE MATERIALS AND WORK AREA AND PROTECTING THE WORK.
4. OBTAIN ENGINEER'S PERMISSION FOR ALL OPENINGS, SLEEVES AND SLOTS OTHER THAN SHOWN ON THE STRUCTURAL DRAWINGS. WHERE DOWELS, ANCHOR BOLTS, ETC., ARE SHOWN PROJECTING INTO MASONRY, BUILD THESE INTO MASONRY VOIDS WITH GROUT.
5. ALL MASONRY SHALL BE SET WITH FULLY FILLED JOINTS.
6. CELLS TO BE REINFORCED SHALL BE KEPT CLEAN OF MORTAR.
7. PROVIDE A MINIMUM 25mm GROUT UNDER ALL WALL PLATES AND BASE PLATES AND BEAR ON SOLID MASONRY OF 400mm (MINIMUM) DEPTH.
8. PROVIDE AND INSTALL LINTELS OVER ALL OPENINGS OR RECESSES IN MASONRY WALLS INCLUDING THOSE FOR MECHANICAL OR ELECTRICAL SERVICES OR EQUIPMENT, IN ACCORDANCE WITH THE REQUIREMENTS OF THE LINTEL SCHEDULE.
9. PROVIDE A MINIMUM LENGTH OF 200mm OF 100% SOLID MASONRY UNITS FOR BEARING OF STEEL, CONCRETE OR REINFORCED MASONRY LINTELS. FILL LINTELS WITH 20MPa CONCRETE GROUT CONTAINING 10mm AGGREGATE.
10. ALL MASONRY WALLS TO BE REINFORCED WITH 15M @ 1200 UNLESS NOTED OTHERWISE.
11. THE CONCRETE CONTRACTOR MUST PROVIDE REINFORCING DOWELS PROJECTING FROM CAST-IN-PLACE CONCRETE INTO BLOCK WALLS TO MATCH VERTICAL REINFORCING IN BLOCK WALLS. LAPS IN REINFORCING:

WIRE REINFORCING 150
10M 600
15M 750
20M 950
25M 1100
30M 1600
35M MECHANICAL SPLICE

12. FILL CELLS CONTAINING VERTICAL REINFORCING WITH 20MPa CONCRETE GROUT CONTAINING 10mm AGGREGATE AND UP TO 250mm SLUMP. VIBRATE OR PUDLE TO FILL CELLS COMPLETELY. USING JOINT MORTAR FOR FILLING THE CELLS IS NOT ACCEPTABLE AND WILL REQUIRE RECONSTRUCTION OF WALL.
13. FILL CELLS IN 1500mm HIGH LIFTS OR IF CLEANOUTS ARE PROVIDED IN 2400mm HIGH LIFTS.
14. PROVIDE CONTINUOUS LADDER TYPE JOINT REINFORCING AT 400mm c/c AND USE "CORNER-LOK" AT ALL WALL INTERSECTIONS. REINFORCING TO BE GALVANIZED TO ASTM A153 CLASS B2 (458g/m²).

FOR CAVITY WALL AND SINGLE WYTHE 3.65mm Ø WIRES (9 GAUGE)
FOR COMPOSITE WYTHE 4.76mm Ø WIRES
15. ALL METAL ANCHORS TO SECURE WALLS EXPOSED TO WEATHER SHALL BE HOT DIP GALVANIZED.
16. ANCHOR MASONRY TO STEEL COLUMNS WITH STEEL STRAP PLATE AS INDICATED.
17. JOINTS IN MASONRY SHALL BE LOCATED AT LEAST 300mm FROM ANY OPENING IN THE WALL, UNLESS SPECIFICALLY NOTED OTHERWISE.

CAST-IN-PLACE CONCRETE:

1. DO CONCRETE WORK IN ACCORDANCE WITH THE LATEST VERSION OF THE APPLICABLE CODES AND STANDARDS.
2. SUBMIT REINFORCING DIAGRAMS BEFORE FABRICATION FOR REVIEW BY THE ENGINEER.
3. REINFORCING IS TO BE GENERALLY DETAILED IN ACCORDANCE WITH THE RSIC MANUAL OF STANDARD PRACTICE (LATEST EDITION). SPLICES SHALL BE CLASS 'B' TENSION LAP SPLICES.
4. THE CLEAR DISTANCE BETWEEN REINFORCING STEEL AND SURFACE OF CONCRETE SHALL BE AS FOLLOWS:

FORMED CONCRETE NOT EXPOSED TO WATER OR WEATHER: 40mm
FORMED CONCRETE EXPOSED TO WATER, WEATHER OR EARTH: 50mm
CONCRETE PLACED AGAINST MUD MAT: 50mm
CONCRETE PLACED AGAINST EARTH: 75mm
5. UNLESS INDICATED OTHERWISE, ALL DOWELS SHALL HAVE THE SAME SIZE AND SPACING AS THE REINFORCING STEEL TO WHICH THEY ARE SPLICED.
6. ALL REINFORCING STEEL PLACEMENT TO BE INSPECTED BY THE ENGINEER BEFORE PLACING THE CONCRETE.
7. NO WELDING OF REINFORCING BARS SHALL BE PERMITTED, UNLESS APPROVAL IS OBTAINED FROM THE ENGINEER PRIOR TO CONSTRUCTION.
8. DO NOT SAWCUT THE SLAB ON GRADE OR OTHER FLOORS, UNLESS SPECIFICALLY SHOWN AND DETAILED ON THE DESIGN DRAWINGS.
9. ALL REINFORCING BARS SHALL BE SUPPORTED IN THE FORMS AND SPACED WITH STANDARD ACCESSORIES SO THAT THERE IS NO MOVEMENT DURING CONCRETE PLACEMENT.
10. PROVIDE REINFORCING DOWELS PROJECTING FROM CAST-IN-PLACE CONCRETE INTO BLOCK WALLS TO MATCH VERTICAL REINFORCING IN BLOCK WALLS.

DELEGATED DESIGN:

1. SUBMIT SHOP DRAWINGS FOR COMPONENTS REQUIRING DELEGATED DESIGN UNDER THE SEAL AND SIGNATURE OF THE ENGINEER RESPONSIBLE FOR THE DESIGN TO THE PRIME CONSULTANT FOR COORDINATION REVIEW.
2. SHOP DRAWINGS SHALL CLEARLY INDICATE ANY LOADS IMPARTED TO THE STRUCTURE.
3. CONNECTIONS TO THE PRIMARY STRUCTURE SHALL ACCOMMODATE DEFLECTIONS IN THE PRIMARY STRUCTURE. THE CONTRACTOR MAY SEEK GUIDANCE FROM THE ENGINEER OF RECORD AS TO DESIGN LOADS, DEFLECTIONS, ETC.

EXISTING STRUCTURES:

1. DIMENSIONS PERTAINING TO EXISTING STRUCTURES SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR, PRIOR TO THE COMMENCEMENT OF CONSTRUCTION AND FABRICATION. CIMA IS TO BE NOTIFIED OF ANY DISCREPANCIES.
2. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, REPAIR ANY DAMAGE TO THE EXISTING STRUCTURE, EQUIPMENT & FINISHES CAUSED BY THE CONSTRUCTION ACTIVITIES. REPAIRS SHALL BE SUBJECT TO THE ARCHITECT'S APPROVAL.

SHORING

1. THE SITE CONDITIONS WILL NOT PERMIT AN OPEN EXCAVATION.
2. ALL SIDES OF THE EXCAVATION MUST BE BRACED OR SHORED TO MAINTAIN STRICT ADHERENCE TO THE OCCUPATIONAL HEALTH AND SAFETY ACT.
3. THE LINE OF THE SHORING SHOWN ON THE DRAWING HAS BEEN PROVIDED AS A GUIDE INDICATING THE GENERAL EXTENT AND LOCATION OF THE SYSTEM. HOWEVER, THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF A SYSTEM TO SUIT THEIR CONSTRUCTION REQUIREMENTS.
4. THE CONTRACTOR SHALL ENGAGE A STRUCTURAL ENGINEER TO DESIGN AND INSPECT THE SHORING SYSTEM.
5. THE CONTRACTOR SHALL ENGAGE A GEOTECHNICAL ENGINEER TO REVIEW AND CARRY OUT AN ASSESSMENT OF THE SITE CONDITIONS. BASED ON THIS WORK AND A REVIEW OF THE AVAILABLE GEOTECHNICAL INFORMATION, THE GEOTECHNICAL ENGINEER SHALL PROVIDE A DESIGN INFORMATION TO THE STRUCTURAL ENGINEER ENGAGED BY THE CONTRACTOR TO DESIGN THE SHORING SYSTEM.
6. THE STRUCTURAL ENGINEER SHALL SUBMIT SEALED COPIES OF THE DESIGN DRAWINGS FOR REVIEW BY THE OWNER'S ENGINEER BEFORE PROCEEDING WITH THE WORK.
7. THE CONTRACTOR SHALL NOT DISTURB OR DAMAGE ADJACENT STRUCTURES DURING EXCAVATION CONSTRUCTION, BACKFILL OR COMPACTION OPERATIONS, INCLUDING THE DRIVING OR REMOVAL OF ANY SHORING.
8. THE CONTRACTOR SHALL PROVIDE FOR CONDUCTING PRECONDITION SURVEYS OF EXISTING ADJACENT BUILDINGS AND FOR DESIGNING APPROPRIATE CONSTRUCTION METHODS TO AVOID DAMAGE TO THESE BUILDINGS AND/OR PREMISES.

CLIMATE DATA FOR OSHAWA				
IMPORTANCE CATEGORY: HIGH				
LOAD TYPE		LOAD		IMPORTANCE FACTOR
SNOW	GROUND SNOW LOAD (1/50 YEARS)	Ss	1.0 kPa	1.5
	ASSOCIATED RAIN LOAD (1/50 YEARS)	Sr	0.4 kPa	
WIND	REFERENCE VELOCITY WIND PRESSURE (1/50 YEARS)	q	0.48 kPa	1.5
	PEAK GROUND ACCELERATION	PGA (E)	0.251	
EARTHQUAKE	HORIZONTAL SPECTRAL ACCELERATION VALUES (2% PROBABILITY OF EXCEEDANCE IN 50 YEARS)	Sa(0.2,E)	0.402	1.5
		Sa(0.5,E)	0.222	
		Sa(1.0,E)	0.105	
		Sa(2.0,E)	0.022	
		Sa(5.0,E)	0.028	
		Sa(10.0,E)	0.008	
	SITE CLASS (ASSUMED)	E		

ABBREVIATIONS

ADDD	ADDITIONAL	L	LENGTH OF REBAR
AGGR	AGGREGATE	LG	LONG
ALT	ALTERNATE	LL	LOWER LEVEL or LIVE LOAD
ALUM	ALUMINUM	LLH	LONG LEG HORIZONTAL
APPROX	APPROXIMATE	LLV	LONG LEG VERTICAL
ARCH	ARCHITECTURAL	LNLT	LINTEL
B/	BOTTOM OF	LP	LOW POINT
BLDG	BUILDING	LW	LONG WAY
BM	BEAM	MAX	MAXIMUM
BPL	BASE PLATE	MC	MOMENT CONNECTION
BLL	BOTTOM LOWER LAYER	MECH	MECHANICAL
BOT	BOTTOM	MEMB	MEMBRANE
BRG	BEARING	MEZZ	MEZZANINE
BR	BRACING	MID	MIDDLE
BRDG	BRIDGING	MIN	MINIMUM
BS	BOTH SIDES	MIRR	MIRROR
BTWN	BETWEEN	MISC	MISCELLANEOUS
BUL	BOTTOM UPPER LAYER	N/A	NOT APPLICABLE
BW	BOTH WAYS	NTS	NOT TO SCALE
C/C	CENTER TO CENTER	OC	ON CENTER
C/W	COMPLETE WITH	OD	OUTSIDE DIAMETER
CANT	CANTILEVER	OF	OUTSIDE FACE
CIP	CAST-IN-PLACE	OH	OVERHEAD
CL	CENTERLINE	OPNG	OPENINGS
CL or CL	COMPLETE PENETRATION	OPP	OPPOSITE
CLR	CLEAR	OR	OUTSIDE RADIUS
COL	COLUMN	OWVSJ	OPEN WEB STEEL JOIST
CONC	CONCRETE	PCP	PRECAST CONCRETE PANEL
CONN	CONNECTION	PERP	PERPENDICULAR
CONT	CONTINUOUS	PL	PLATE
COORD	COORDINATE	±	PLUS / MINUS
CTR	CENTRE	PRCST	PRECAST
CTRL JT	CONTROL JOINT	PROC	PROCESS
DEMO	DEMOLISH	PSI	POUNDS PER SQUARE INCH
DET	DETAIL	PT CONC	POST-TENSIONED CONCRETE
DIA	DIAMETER	QTY	QUANTITY
DIAG	DIAGONAL	R	RADIUS
DIM	DIMENSION	R/W	REINFORCED WITH
DIST	DISTANCE	REF	REFERENCE
DL	DEAD LOAD	REINF	REINFORCEMENT
-DO-	REPEAT INSTRUCTION	REQD	REQUIRED
DWG	DRAWING	RWL	RAIN WATER LEADER
DWL	DOWEL	SAW	SHORT WAY
EF	EACH FACE	SCD	SCUPPER DRAIN
EJ	EXPANSION JOINT	SCHED	SCHEDULE
ELEC	ELECTRICAL	SECT	SECTION
EL	ELEVATION	SF	STEP FOOTING
EMB	EMBEDMENT	SHT	SHEET
EQ	EQUAL	SIM	SIMILAR
EQUIP	EQUIPMENT	SOG	SLAB ON GRADE
EQUIV	EQUIVALENT	SPEC	SPECIFICATION
E/S	EXISTING	STAG	STANDARD PROCTOR
EX	EXISTING	SOG	SLAB ON GRADE
EXP	EXPANSION	SPC	SPECIFICATION
EXT	EXTERIOR	SPMD	STANDARD PROCTOR
EW	EACH WAY	SS	STAINLESS STEEL
FD	FLOOR DRAIN	STIF	STIFFENER
FDN	FOUNDATION	STIR	STIRRUP
FMC	FULL MOMENT CONNECTION	STD	STANDARD
FRMG	FRAMING	STR	STRINGER
FTG	FOOTING	STA6	STAGGERED
GA	GAUGE	STRUCT	STRUCTURAL
GALV	GALVANIZED	SYMM	SYMMETRICAL
GIR	GIRDER	TEMP	TEMPORARY
GL	GRID LINE	THK	THICK
GR	GRADE	T/	TOP OF
GR BM	GRADE BEAM	THRU	THROUGH
HC	HOLLOW CORE	TJ	TIE JOIST
HCMU	HOLLOW CONCRETE MASONRY UNIT	TLL	TOP LOWER LAYER
HEF	HORIZONTAL EACH FACE	TUL	TOP UPPER LAYER
HIF	HORIZONTAL INSIDE FACE	TYP	TYPICAL
HOE	HORIZONTAL OUTSIDE FACE	T&B	TOP AND BOTTOM
H1E	HOOK ONE END	UNO	UNLESS NOTED OTHERWISE
H2E	HOOK TWO ENDS	US	UNDERSIDE
HL	HIGH LEVEL	VB	VERTICAL BRACING
HORIZ	HORIZONTAL	VEF	VERTICAL EACH FACE
HP	HIGH POINT	VERT	VERTICAL
HSS	HOLLOW STRUCTURAL STEEL	VIF	VERTICAL INSIDE FACE
ID	INTERNAL DIAMETER	VOF	VERTICAL OUTSIDE FACE
IF	INSIDE FACE	W/	WITH
IFC	ISSUED FOR CONSTRUCTION	W/O	WITHOUT
IFT	ISSUED FOR TENDER	WPL	WALL PLATE
INT	INTERIOR	WWM	WELDED WIRE MESH
INV	INVERT	XBR	CROSS BRACE
KO	KNOCK OUT	XSECT	CROSS SECTION

DISCLAIMER:
This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+'s and its client, as required by law or for use by governmental reviewing agencies. CIMA+'s accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.



DESIGNED BY: _____ APPROVED BY: _____

CONSULTANT(S): _____

ENGINEER:
CIMA+
415 Baseline Road West
Bowmanville, ON L1C 5M2
T 905.697.4464 F 905.697.0443
www.cima.ca

CLIENT:
WAVERLY PS
100 Waverly St S
Oshawa, ON L1J 5V1

PROJECT NAME:
**WAVERLY PS
ELEVATOR RENOVATION**

SHEET TITLE:
GENERAL NOTES

DISCIPLINE	
STRUCTURAL	
DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No.: A0001195	DRAWING No.:
SHEET No.: of	S100

TITLER:BLOCK 24x38 VERT ENG

BLOCK LINTEL SCHEDULE

WALL THK	UP TO 1200 mm		1200 mm TO 2030 mm	
	REINF.	D	REINF.	D
140 mm	1 -10M T&B	390 mm	1 -10M T&B	390 mm
190 mm	1 -10M T&B	390 mm	1 -10M T&B	390 mm
240 mm	1 -10M T&B	390 mm	2 -10M T&B	390 mm

1. MIN BEARING FOR BLOCK LINTEL SHALL BE 200 UNO.
2. FILL VOIDS OR LINTEL BLOCKS W/ 20 MPa CONC. MORTAR IS NOT ACCEPTABLE.
3. WHEN 'T' IS SMALLER THAN 'I', ABOVE LINTEL SCHEDULE DOES NOT APPLY. REFER TO PLAN OR THE STEEL LINTEL SCHEDULE.

U/S OF FLOOR SLABS, BEAMS & ANY OTHER SOURCE OF LOADING BEARING ON MASONRY WALL.

OPENING OR RECESS IN WALL

MASONRY WALL

BLOCK LINTEL LENGTH [LB]

50

TOP BAR

BOT. BAR

200

CLEAR SPAN

200

1 BLOCK LINTEL SCHEDULE

STEEL LINTEL SCHEDULE

CLEAR SPAN	UP TO 1200 mm	1200 mm TO 1800 mm	1800 mm TO 2100 mm	ARRANGEMENT
90 WALL	L89x89x7.9	L127x89x7.9	L152x89x7.9	
140 WALL	2 - L64x64x7.9	2 - L89x64x7.9	W200x27 + PL 6	
190 WALL	2 - L89x89x7.9	2 - L127x89x7.9	2L - 152x89x7.9	
240 WALL	2 - L102x102x7.9	2 - L152x102x7.9	2L - 152x102x7.9	
290 WALL	2 - L89x89x7.9	3 - L127x89x7.9	3L - 152x89x7.9	
UP TO 3200	W200x27 + PL 6 THK IN CENTER OF WALL			SEE DETAIL

1. PAIR OF LINTEL ANGLES TO BE STITCH WELDED (T&B) @ 600 mm C/C
2. MIN BEARING FOR STEEL ANGLES SHALL BE 150 mm, UNO
3. FOR LINTELS ABUTTING STEEL COLS, CONC WALLS OR OTHER COLS PROVIDE L89x89x9.5 FASTENED TO ABUTMENT.
4. ALL ANGLES SHALL BE LLV, UNO.
5. ALL LOOSE ANGLES SHALL BE HOT DIPPED GALVANIZED, UNO.

STEEL LINTEL SCHEDULE

CLEAR SPAN	ARRANGEMENT	REMARKS
2100 TO 3600	W200x27 + PL 6 U.N.O. THKICK IN CENTER OF WALL	SEE DETAIL

NOTE:
MINIMUM BEARING FOR STEEL ANGLES SHALL BE 300mm, UNO.

WALL VERTICAL REBAR

16Ø x 100 LONG HDG NELSON STUDS WELDED TO BEAM FLANGE @ 600 o/c AND GROUTED TIGHT INTO BLOCK

CUT BLOCK TO SUIT

W200x27 HDG

PROVIDE MASONRY HDG CLIPS ON BEAM WEB @ EVERY SECOND BLOCK

6 THK CONTINUOUS GALVANIZED PLATE WELDED TO W200. WIDTH TO SUIT BLOCK WALL. BEARING 200 MIN. ON EACH SIDE.

STEEL LINTEL FOR OPENINGS BETWEEN 2100 & 3600

2 LINTEL STEEL SCHEDULE

FOR WALL REINF SIZE & SPACING, SEE PLANS & SECTIONS

MASONRY LIFT HEIGHT = 1500

LAP SPLICE

MAX REBAR LENGTH PER LIFT

REPEAT THROUGH FULL HEIGHT OF WALL

LAP SPLICE	MAX REBAR LENGTH
10M	500
15M	700
20M	850
25M	1100

3 BLOCK WALL REBAR LAP

SCALE: 1 : 20

NOTE: PREFABRICATED 'T' & 'L' REINF FOR CORNERS MUST BE PROVIDED

FULL HEIGHT VERT BARS, SIZE TO MATCH MAIN VERT REINF

LADDER REINF OR EQUAL @ 400 OC VERT SPACING, GALV

INTERSECTING WALLS

NOTE: BLOCK REINF MUST BE LAPPED ONE COMPLETE SQUARE SECTION OF REINF AS SHOWN

LADDER REINF OR EQUAL @ 400 OC VERT SPACING, GALV

BLOCK JOINT REINFORCING LAP

FULL HEIGHT VERT BARS, SIZE TO MATCH MAIN VERT REINF

AT OPENINGS AND CONTROL JOINTS

4 TYPICAL BLOCK WALL REINFORCEMENT

SCALE: 1 : 20

STANDARD HOOK

CLASS 'B' TENSION LAP SPLICE

STANDARD HOOK

INTERSECTING WALLS

WALL CORNER

5 WALL CORNER & INTERSECTION

SCALE: 1 : 20

PROVIDE WALL LATERAL SUPPORT. SEE TYPICAL DETAIL

BOND BEAM REINF. W/ 2-15M CONT.

SEE PLANS FOR REINF.

NON LOAD BEARING MASONRY PARTITION WALL

15M DWLS AT VERT BAR LOCATION

10M @ 300

NEW SLAB

10M @ 300 DRILL AND GROUT 75mm C/W HILTI HIT-HY 200 V3

EX. SLAB

6 MIL POLYETHYLENE SHEET

50 THK MUD SLAB

150 150 450 150 150

6 SLAB THICKENING UNDER BLOCK WALLS

SCALE: 1 : 20

SEALANT AND BACKER ROD

COMPRESSIBLE JOINT FILLER

LADDER REINFORCING, DISCONTINUOUS AT CONTROL JOINTS

FULL HEIGHT VERTICAL MAIN BARS TO MATCH SIZES ON PLAN GROUTED SOLID INTO CORES

15M x 300 LONG @ EVERY 400 o/c IN GREASED PVC SLEEVE IN GROUTED CELLS TO PERMIT IN-PLANE HORIZONTAL MOVEMENT. NOTCH BLOCK AS REQUIRED.

7 BLOCK WALL CONTROL JOINT

7 BLOCK WALL CONTROL JOINT

SCALE: 1 : 10

NEW SOG INFILL TO MATCH EXIST DEPTH, MIN 100

WWM 102x102 - MW 25.7 / MW 25.7

EX. SLAB

NEW EMBEDDED SERVICES, SEE MECH & ELEC

10M@400 x 400 LONG. EMBED 100 C/W HILTI HIT-HY 200 V3

GRANULAR A, COMPACT TO 98% SPMD

8 NEW SERVICES UNDER SLAB (SLAB ON GRADE INFILL)

SCALE: 1 : 10

T

T/3 T/3 T/3

10 CONT. REBAR TIED TO WATERSTOP AND MAIN REINFORCEMENT @ 500 o/c. TYP.

CONSTRUCTION JOINT WITH PVC WATERSTOP. TYP. SEE PROJECT SPECIFICATION

T/6 15 MIN. 50 MAX.

TYPICAL WATERSTOP INSTALLATION DETAILS AT THE INTERSECTION OF SLABS AND WALLS

9 DETAIL

SCALE: 1 : 10

DISCLAIMER:
This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.



DESIGNED BY: _____ APPROVED BY: _____

CONSULTANT(S):

ENGINEER:

CIMA+

415 Baseline Road West
Bowmanville, ON L1C 5M2
T 905.697.4464 F 905.697.0443
www.cima.ca

CLIENT:

WAVERLY PS

100 Waverly St S Oshawa, ON L1J 5V1

PROJECT NAME:

WAVERLY PS ELEVATOR RENOVATION

SHEET TITLE:


TYPICAL DETAILS

DISCIPLINE: **STRUCTURAL**

DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No: A001195	DRAWING No: S200
SHEET No: 2 of 9	


PRINT DATE: 2026-03-16 4:41:33 PM
PATH: A:\work\Draws\DDSB\Accessibility Projects\A001195\Waverly PS\S231.dwg

TITLEBLOCK 24x38 VERT ENG
 PRINT DATE: 2026-03-16 4:41:24 PM
 PATH: A:\work\Drawings\DDSB\Accessibility Projects\A001199\Waverly PS-S231.rvt




1 OPENINGS IN FLOOR AND ROOF DECK
 S201 SCALE: 1 : 25


NOTE:
 1. FOR EXACT SIZE AND LOADS AT OPENINGS, SEE ARCHITECTURAL AND MECHANICAL DRAWINGS.
 2. UP TO 2000mm TO BE C150x12




2 SECTION
 S201 SCALE: 1 : 10




3 EXISTING JOIST REINFORCING
 S201 SCALE: 1 : 10




4 LATERAL SUPPORT OF BLOCK WALL PERPENDICULAR TO BEAMS OR JOISTS
 S201 SCALE: 1 : 20




5 LATERAL SUPPORT OF BLOCK WALL PARALLEL TO JOISTS
 S201 SCALE: 1 : 20



6 LATERAL SUPPORT FOR MASONRY WALL
 S201 SCALE: 1 : 10



7 LATERAL SUPPORT OF BLOCK WALL PARALLEL TO BEAMS
 S201 SCALE: 1 : 20



8 DETAIL
 S201 SCALE: 1 : 5

TENSION LAP SPLICES - CLASS "A" (LTA)

BAR SIZE	TYPE 1 - f _c (MPa)					TYPE 2 - f _c (MPa)						
	20	25	30	35	40	20	25	30	35	40	45	50
10M	370	330	300	280	260	250	240	490	440	400	370	350
15M	520	470	430	390	370	350	330	690	620	570	520	490
20M	630	570	520	480	450	420	400	840	750	690	640	600
25M	1020	910	830	770	720	680	650	1360	1210	1110	1030	960
30M	1210	1080	990	910	860	810	770	1610	1440	1320	1220	1140
35M	1440	1290	1180	1090	1020	960	910	1920	1720	1570	1450	1360
45M	TENSION LAP SPLICES NOT PERMITTED					TENSION LAP SPLICES NOT PERMITTED						
55M	TENSION LAP SPLICES NOT PERMITTED					TENSION LAP SPLICES NOT PERMITTED						

TENSION LAP SPLICES - CLASS "B" (LTB)

BAR SIZE	TYPE 1 - f _c (MPa)					TYPE 2 - f _c (MPa)						
	20	25	30	35	40	20	25	30	35	40	45	50
10M	480	430	390	360	340	320	300	640	570	520	480	450
15M	670	600	550	510	480	450	430	900	800	730	680	640
20M	820	740	670	620	580	550	520	1090	980	890	830	770
25M	1320	1180	1080	1000	940	880	840	1760	1580	1440	1330	1250
30M	1570	1400	1280	1190	1110	1050	990	2090	1870	1710	1580	1480
35M	1870	1680	1530	1420	1330	1250	1190	2500	2230	2040	1890	1770
45M	TENSION LAP SPLICES NOT PERMITTED					TENSION LAP SPLICES NOT PERMITTED						
55M	TENSION LAP SPLICES NOT PERMITTED					TENSION LAP SPLICES NOT PERMITTED						

TENSION LAP SPLICE NOTES

- REFERENCE CODE CAN/CSA A23.3-19.
- TABLES ARE IN MILLIMETERS, ϕ_b = BAR DIAMETER.
- TENSION LAP SPLICES:
 - CLASS "A": APPLICABLE WHEN REINFORCING PROVIDED IS AT LEAST TWICE THAT REQUIRED BY ANALYSIS AND LESS THAN ONE-HALF OF THE TOTAL REINF. IS SPLICED WITHIN THE REQUIRED LAP LENGTH.
 - CLASS "B": APPLICABLE EVERYWHERE EXCEPT WHERE CLASS "A" CAN BE USED.
 - TENSION LAP SPLICE LENGTH SHALL NOT BE LESS THAN 300mm.
 - TENSION LAP SPLICES FOR BARS LARGER THAN 35M ARE NOT PERMITTED.
 - TYPES 1 AND 2 ARE THE SAME AS TENSION DEVELOPMENT TYPES - SEE NOTES FOR DEVELOPMENT OF REINFORCING BARS.
 - TENSION LAP SPLICES LISTED IN TENSION LAP SPLICE TABLES SHALL BE MULTIPLIED WITH THE FOLLOWING FACTORS FOR:

MODIFICATION FACTOR	
k1 - TOP BARS HAVING MORE THAN 300mm OF FRESH CONCRETE CAST BELOW THE DEVELOPMENT LENGTH.	1.3
k2 - FOR EPOXY-COATED REINFORCEMENT WITH CLEAR COVER LESS THAN 3 ϕ_b OR WITH CLEAR SPACING BETWEEN BARS BEING DEVELOPED LESS THAN 6 ϕ_b .	1.5
- FOR ALL OTHER EPOXY-COATED REINFORCEMENT	1.2
k3 - FOR STRUCTURAL LOW-DENSITY CONCRETE	1.3
- FOR STRUCTURAL SEMI-LOW-DENSITY CONCRETE	1.2

 THE PRODUCT OF k1k2 NEED TO BE TAKEN GREATER THAN 1.7.
- G. BARS SPLICED BY NON-CONTACT LAP SPLICES SHALL NOT HAVE A TRANSVERSE SPACING NOT EXCEEDING THE LESSER OF ONE-FIFTH OF THE REQUIRED LAP SPLICE LENGTH OR 150mm.
- H. LAP SPLICES OF BARS IN BUNDLE SHALL BE BASED ON THE LAP SPLICE LENGTH REQUIRED FOR INDIVIDUAL BARS WITHIN THE BUNDLE. INCREASED 10% FOR A 2 BAR BUNDLE INCREASED 20% FOR 3 BAR BUNDLES AND 33% FOR A 4 BAR BUNDLE. ENTIRE BUNDLE SHALL NOT BE LAP SPLICED WITHIN ONE LAP LENGTH.

COMPRESSION LAP SPLICES (Lc)


BAR SIZE	f _c < 20 MPa			f _c > 20 MPa		
	OPEN	ENCLOSED		OPEN	ENCLOSED	
		TIES	SPIRAL		TIES	SPIRAL
10M	440	370	330	330	300	300
15M	630	520	470	470	390	360
20M	760	630	570	570	480	430
25M	980	820	740	740	620	560
30M	1170	970	880	880	730	660
35M	1390	1160	1040	1040	870	790
45M	NOTE 4					
55M	NOTE 4					

NOTES FOR COMPRESSION LAP SPLICES OF REINFORCING BARS

- REF CODE CAN/CSA A23.3-19.
- TABLES ARE IN MILLIMETERS.
- COMPRESSION LAP SPLICES:
 - SHALL NOT BE LESS THAN 300mm
 - WHEN BARS OF DIFFERENT SIZE ARE LAP SPLICED IN COMPRESSION, SPLICE LENGTH SHALL BE THE LARGER OF EITHER DEVELOPMENT LENGTH OF THE LARGER BAR, OR SPLICE LENGTH OF THE SMALLER BAR. LAP SPLICES OF 35M BARS AND SMALLER BARS ARE PERMITTED TO 45M AND 55M BARS.
 - TIED REINFORCED MEMBERS ARE DEFINED WHERE TIES THROUGHOUT THE LAP SPLICE LENGTH HAVE AN EFFECTIVE AREA NOT LESS THAN DEFINED IN CAN/CSA A23.3-19, CLAUSE 12.17.3.4.
- LAP SPLICES NOT PERMITTED, USE WELDED SPLICES OR MECHANICAL CONNECTIONS.

MAXIMUM OFFSET

BAR SIZE	BAR ϕ (mm)	H (mm)	C (mm)
20M	19.5	60	240
25M	25.2	70	270
30M	29.9	80	300
35M	35.7	90	330
45M	43.7	LAP SPLICES NOT PERMITTED	
55M	56.4	LAP SPLICES NOT PERMITTED	



DISCLAIMER:
 This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.

STAMPS:

DESIGNED BY: APPROVED BY:

CONSULTANT(S):



ENGINEER:
CIMA+
 415 Baseline Road West
 Bowmanville, ON L1C 5M2
 T 905.697.4464 F 905.697.0443
 www.cima.ca

CLIENT:
WAVERLY PS
 100 Waverly St S Oshawa, ON L1J 5V1


PROJECT NAME:
WAVERLY PS ELEVATOR RENOVATION

SHEET TITLE:
TYPICAL DETAILS


DISCIPLINE:
STRUCTURAL

DRAWER:	SCALE:
E.E. & K.L.	AS NOTED
DESIGNER:	DATE:
B.S.	03/16/2026
APPROVER:	CHECKER:
S.Y.	S.Y.
PROJECT No.:	DRAWING No.:
A001195	S201
SHEET No.:	3 of 9

TITLEBLOCK 24x36 VERT ENG
 PRINT DATE: 2026-03-16 4:41:24 PM
 PATH: A:\work\Drawings\DDSB\Accessibility Projects\A001195\Waverly PS_S231.rvt



1 PARTIAL EXISTING GROUND FLOOR PLAN - SLAB DEMO
 S300 SCALE: 1 : 50



2 PARTIAL EXISTING SECOND FLOOR FRAMING PLAN - SLAB & JOIST DEMO
 S300 SCALE: 1 : 50

- NOTES:**
- EXISTING JOIST SHOE TO REMAIN TO SUPPORT EXISTING STEEL DECK BETWEEN EX. BEAM AND DECK. TYP. U.N.O. BOTH ENDS.
 - PROVIDE SHORING TO SUPPORT EXISTING FLOOR. SHORING TO REMAIN IN PLACE UNTIL NEW STRUCTURE HAS BEEN COMPLETED.
 - SUBMIT SHORING DRAWINGS TO THE ENGINEER FOR REVIEW. SHORING TO BE DESIGNED BY AN ENGINEER LICENSED IN THE PROVINCE OF ONTARIO.

DISCLAIMER:
 This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.

STAMPS:

DESIGNED BY: _____ APPROVED BY: _____

CONSULTANT(S):

ENGINEER:

415 Baseline Road West
 Bowmanville, ON L1C 5M2
 T 905.697.4464 F 905.697.0443
 www.cima.ca

CLIENT:

WAVERLY PS
 100 Waverly St S
 Oshawa, ON L1J 5V1

PROJECT NAME:

**WAVERLY PS
 ELEVATOR RENOVATION**

SHEET TITLE:


DEMOLITION INFO

DISCIPLINE:

STRUCTURAL

DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No.: A0001195	DRAWING No.: S300
SHEET No.: _____	of _____

TITLEBLOCK 24x36 VERT ENG
 PRINT DATE: 2026-03-16 4:41:24 PM
 PATH: Autocad Docs\DDSB Accessibility Projects\A001199-Waverly PS-S23.rvt



1 EXISTING PARTIAL FOUNDATION AND GROUND FLOOR PLAN
 S400 SCALE: 1 : 25

DISCLAIMER:
 This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.

STAMPS:

 DESIGNED BY: _____ APPROVED BY: _____

CONSULTANT(S):

ENGINEER:


 415 Baseline Road West
 Bowmanville, ON L1C 5M2
 T 905.697.4464 F 905.697.0443
 www.cima.ca

CLIENT:
WAVERLY PS
 100 Waverly St S
 Oshawa, ON L1J 5V1

PROJECT NAME:
**WAVERLY PS
 ELEVATOR RENOVATION**

SHEET TITLE:
**EXISTING PARTIAL FOUNDATION
 PLAN**

DISCIPLINE	
STRUCTURAL	
DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No.: A001195	DRAWING No.:
SHEET No.: _____	S400
of _____	



1 EXISTING PARTIAL SECOND FLOOR FRAMING
 S401 SCALE: 1 : 25

BEARING PLATES:
BP-1
 160 X 400 X 12 mm BEARING PLATE
 PROVIDE POCKET IN WALL TO ACCOMMODATE NEW STEEL BEAM.
 NEW W200 TO BE WELDED TO BEARING PLATE.
 FULLY GROUT 400mm MIN BELOW BEARING PLATE.
 PROVIDE 30mm NON-SHRINK GROUT BETWEEN WALL AND BEARING PLATE.

NOTES:
 1. CONNECT NEW STEEL TO EXISTING STEEL BEAMS FOR THE FOLLOWING LOADS:
 V₁ = 25 kN

SECOND FLOOR DESIGN LOADS (UNFACTORED):
DEAD LOAD:
 DESIGN LOADS (UNFACTORED):
 DEAD: 0.10 kPa
 FLOORING: 0.20 kPa
 SUSPENDED CEILING: 0.25 kPa
 MECH AND ELEC ALLOWANCE: 1.00 kPa
 PARTITION ALLOWANCE: 1.52 kPa
 CONCRETE SLAB: 3.07 kPa
 TOTAL: 4.80 kPa
 PLUS SELF WEIGHT OF STRUCTURAL STEEL
 LIVE: 4.80 kPa

DISCLAIMER:
 This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.

STAMPS:

DESIGNED BY: *S. L. Young*
 APPROVED BY: *S. L. Young*

PROFESSIONAL ENGINEER
 S. L. YOUNG
 100212163
 03/16/2026
 PROVINCE OF ONTARIO

CONSULTANT(S):

ENGINEER:

CIMA+
 415 Baseline Road West
 Bowmanville, ON L1C 5M2
 T 905.697.4464 F 905.697.0443
 www.cima.ca

CLIENT:

WAVERLY PS
 100 Waverly St S
 Oshawa, ON L1J 5V1

PROJECT NAME:

**WAVERLY PS
 ELEVATOR RENOVATION**

SHEET TITLE:


**EXISTING PARTIAL SECOND
 FLOOR FRAMING PLAN**

DISCIPLINE:

STRUCTURAL

DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No.: A001195	DRAWING No.: S401
SHEET No.: of	

TITLEBLOCK 24x36 VERT ENG
 PRINT DATE: 2026-03-16 4:41:25 PM
 PATH: A:\work\Drawings\DDSB\Accessibility Projects\A001195-Waverly PS-S23.rvt



1 EXISTING PATIAL ROOF FRAMING PLAN
 S402 SCALE: 1 : 25

DISCLAIMER:
 This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	By
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.

STAMPS:

DESIGNED BY

APPROVED BY

CONSULTANT(S):

ENGINEER:

415 Baseline Road West
 Bowmanville, ON L1C 5M2
 T 905.697.4464 F 905.697.0443
 www.cima.ca

CLIENT:

WAVERLY PS
 100 Waverly St S
 Oshawa, ON L1J 5V1

PROJECT NAME:



**WAVERLY PS
 ELEVATOR RENOVATION**

SHEET TITLE:

**EXISTING PARTIAL ROOF FRAMING
 PLAN**

DISCIPLINE	
STRUCTURAL	
DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No.: A001195	DRAWING No.: S402
SHEET No.: of	

TITLEBLOCK 24x36 VERT ENG
 PRINT DATE: 2026-03-16 4:41:35 PM
 PATH: A:\work\Drawings\Accessability Projects\A001199-Waverly PS-S23.rvt



DISCLAIMER:
 This drawing has been prepared for the use of CIMA+'s client and may not be used, reproduced or relied upon by third parties, except as agreed by CIMA+ and its client, as required by law or for use by governmental reviewing agencies. CIMA+ accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without CIMA+'s express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

No.	Date	Description	S.Y.
0	03/16/2026	ISSUED FOR PERMIT & TENDER	S.Y.

STAMPS:

LICENSED PROFESSIONAL ENGINEER
 S. L. YOUNG
 100212163
 03/16/2026
 PROVINCE OF ONTARIO

DESIGNED BY: _____ APPROVED BY: _____

CONSULTANT(S):

ENGINEER:

CIMA+
 415 Baseline Road West
 Bowmanville, ON L1C 5M2
 T 905.697.4464 F 905.697.0443
 www.cima.ca

CLIENT:

WAVERLY PS
 100 Waverly St S
 Oshawa, ON L1J 5V1

PROJECT NAME:

WAVERLY PS ELEVATOR RENOVATION

SHEET TITLE:

SECTIONS

DISCIPLINE: STRUCTURAL

DRAFTER: E.E. & K.L.	SCALE: AS NOTED
DESIGNER: B.S.	DATE: 03/16/2026
APPROVER: S.Y.	CHECKER: S.Y.
PROJECT No.: A0001195	DRAWING No.: S500
SHEET No.: _____	of _____