



Peterborough Victoria  
Northumberland and Clarington  
Catholic District School Board

**PVNC  
Catholic**

**2026-T-10**

## **St. Joseph CES Drainage Improvements**

### **ADDENDUM #2**

This addendum shall form an integral part of the bid documents for the above noted bid and shall be read in conjunction therewith. This addendum shall, however, take precedence over all requirements as it pertains to the particular and specific items noted below.

#### **Additional Information**

**Add (1):**

#### **GENERAL**

- Repaint existing basketball markings on asphalt – see Image 1.
- Maintain location of existing main playground structure. Carefully relocate north slide and post with ladder to east side of playground structure and re-pour foundation as required. Remove and dispose of existing foundation associated with that slide – see Image 2.
- Remove Corkscrew component on main playground structure and dispose of associated foundation. Return equipment to Owner – see Image 3.
- Extend north side of new synthetic rubber surface and timber curb edging to new retaining wall. Maintain minimum 1.8 m from main play structure to new retaining wall.
- Remove all other existing auxiliary play equipment and associated foundations. Return all equipment to owner – see Image 4.

#### **SPECIFICATIONS**

- **SECTION 32 32 16 - Precast Concrete Retaining Walls**

Add subsection:

#### **3.7 Field Quality Control**

1. The independent specialty engineer responsible for the design of precast concrete retaining walls shall:
  1. Conduct periodic field reviews during construction and shall submit field review reports within three days of each visit

2. Following completion of the work, provide the Consultant with a stamped letter certifying that the design and installation meet the requirements set out in the engineered shop drawings.
2. Provide the Independent Specialty Engineer's letters of review and sign-off letters as specified in Section 01 78 00 for precast concrete retaining walls.


## DRAWINGS

- **DRAWING A103 – PART SITE PLAN**
  - Note 1: Top of existing curb portion to be cut down to provide level surface between middle stair landing and adjacent artificial turf area. Wall to be cut down approx. 3" below final grade level and then patched with a suitable concrete repair product to ensure min 2" cover above existing rebar in wall. Top of patched portion to be flush with top of mid stair landing.
- **DRAWING A601 – SECTIONS**
  - Section 2/A601 to indicate new 1.8m high chain link fence to replace existing chain link fence in the same location.

**Add (2):** Addendum No. 2 Prepared by Barry Bryan Associates (5 pages)

**END OF ADDENDUM #2**

**ST. JOSEPH SITE DEVELOPMENT  
ADDENDUM NO.2 -- IMAGE 1**



**REPAINT EXISTING  
BASKETBALL MARKINGS  
ON ASPHALT**

**ST. JOSEPH SITE DEVELOPMENT  
ADDENDUM NO.2 -- IMAGE 2**



**CAREFULLY RELOCATE NORTH SLIDE AND  
POST WITH LADDER TO EAST SIDE OF  
PLAYGROUND STRUCTURE AND RE-POUR  
FOUNDATION AS REQUIRED. REMOVE AND  
DISPOSE OF EXISTING FOUNDATION  
ASSOCIATED WITH SLIDE.**

ST. JOSEPH SITE DEVELOPMENT  
ADDENDUM NO.2 -- IMAGE 3

REMOVE CORKSCREW  
COMPONENT ON MAIN  
PLAYGROUND  
STRUCTURE AND  
RETURN TO OWNER.



**ST. JOSEPH SITE DEVELOPMENT  
ADDENDUM NO.2 -- IMAGE 4**

**REMOVE ALL OTHER  
EXISTING AUXILIARY  
PLAY EQUIPMENT AND  
ASSOCIATED  
FOUNDATIONS. RETURN  
ALL EQUIPMENT TO  
OWNER.**



